

M/s

Date: 1st. August 2023

Notice Inviting Quotation:

Sealed quotation are invited for the following works from experienced bonafied and resourceful outside /inside contractors for the under mentioned works by the The Chief Executive Officer of Tollygunge Club Limited at 120 Deshapran Sasmal Road,Kolkata-700 033

Name of the work: Interior work inside south side rooms of Tolly Terrace blocks at Tollygunge Club Premises,120 Deshapran Sasmal Road,Kolkata-700 033.

Sl no.	Description of work.	Unit	Qty	Rate in figure in Rs.	Rate in words	Total Amount in Rs.	Remarks
A	Golf Theme rooms (West side)						
1	Laminate removing: Removing of laminate from existing furniture with heatgug machine and all addhesive from it and removing of debris from out side of building.	Sft	1920				
2	Veneer cladding: Providing and pasting of veneer after removing the laminate from the existing furniture with 4mm thick approved veneer (Century/Green/Eqv.) with addhesive and necessary hardware fitting as required. (Basic price of Veneer: Rs.200.00 per sft)	Sft	1920				
3	Wall panelling: Providing and making of TV wall panelling with 12mm thick BWP grade ply of Green/Century/Eqv. Brand as per approved design (copy design from Horse theme room) and will be finished with 4mm thick veneer with natural melamine polish and lacquered coating finish with all hardwar and fittings complete.	Sft	240				
4	Polishing of new veneer: Providing and applying of melamine of Asian paints make lacquered polish on all types of furnitureand other surfaces after removing the existing damaged polish with rubbing with sand paper and then application of melamine natural veneer colour polish materials and final finished with lacquered coating to get the smooth and matt finish.	Sft	2225				
5	Duco paint: Providing and applying of duco paint on windows and door frames of main door and toilet door after rubbing the existing paintwith water paper and application of duco paint of approved colour in two coats after NC putty and primer on the surface to get the smoothand matt finish.	Sft	492				

6	Fridge cabinet: Providing and applying of new fridge cabinet with 19mm thick BWP plywood of Green/Century/Eqv.as per approved design and the ply surface will be finished with approved 4mm thick veneer of Green/Century/Eqv. The veneer will be polished with natural melamine polish with lacquered polish. There will be a space for the mini fridge inside cabinet with air passing facility complete with all types of necessary Hardware and fittings complete.	No	6				
7	Repairing of pelmets: Providing necessary ply and hardware and repairing of existing pelmets which has been made for keeping the AC split unit machine.	sft	90				
B	Suite Rooms						
1	Laminate removing: Removing of laminate from existing furniture with heatgug machine and all adhesive from it and removing of debris from out side of building.	Sft	500				
2	Veneer cladding: Providing and pasting of veneer after removing the laminate from the existing furniture with 4mm thick approved veneer (Century/Green/Eqv.) with adhesive and necessary hardware fitting as required. (Basic price of Veneer: Rs.200.00 per sft)	Sft	500				
3	Polishing of existing veneer: Providing and applying of melamine of Asian paints make lacquered polish on all types of furniture and other surfaces after removing the existing damaged polish with rubbing with sand paper and then application of melamine natural veneer colour polish materials and final finished with lacquered coating to get the smooth and matt finish.	Sft	2898				
4	Duco Paint: Providing and applying of duco paint on windows and door frames of main door and toilet door after rubbing the existing paint with water paper and application of duco paint of approved colour in two coats after NC putty and primer on the surface to get the smooth and matt finish.	Sft	1242				
5	Fridge cabinet: Providing and applying of new fridge cabinet with 19mm thick BWP plywood of Green/Century/Eqv.as per approved design and the ply surface will be finished with approved 4mm thick veneer of Green/Century/Eqv. The veneer will be polished with natural melamine polish with lacquered polish. There will be a space for the mini fridge inside cabinet with air passing facility complete with all types of necessary Hardware and fittings complete.	No	6				
6	Repairing of pelmets: Providing necessary ply and hardware and repairing of existing pelmets which has been made for keeping the AC split unit machine.	sft	220				
C	Horse Theme rooms (East side)						
1	Polishing of existing veneer: Providing and applying of melamine of Asian paints make lacquered polish on all types of furniture and other surfaces after removing the existing damaged polish with rubbing with sand paper and then application of melamine natural veneer colour polish materials and final finished with lacquered coating to get the smooth and matt finish.	Sft	2830				

2	Duco paint: Providing and applying of duco paint on windows and door frames of main door and toilet door after rubbing the existing paint with water paper and application of duco paint of approved colour in two coats after NC putty and primer on the surface to get the smooth and matt finish.	Sft	492				
3	Fridge cabinet: Providing and applying of new fridge cabinet with 19mm thick BWP plywood of Green/Century/Eqv. as per approved design and the ply surface will be finished with approved 4mm thick veneer of Green/Century/Eqv. The veneer will be polished with natural melamine polish with lacquered polish. There will be a space for the mini fridge inside cabinet with air passing facility complete with all types of necessary Hardware and fittings complete.	No	6				
4	Repairing of pelmets: Providing necessary ply and hardware and repairing of existing pelmets which has been made for keeping the AC split unit machine.	sft	140				
Total Amount (Excluding GST) Rs.							

Total Amount Rs.

Terms & Condition:

1. Sealed quotation to be submitted at Club Office on or Before 8th August, 2023
2. Completion time : 35 days.
3. Payment will be made against RA bill/ Final bill.
4. Current ESI & PF chalan to be submitted with each bill.
5. In case the work is not completed on or before the date of completion stated above a penalty of 0.5% of the total bill value will be deducted per week of the incomplete portion of work up to a maximum 5% of the incomplete portion of work.
6. 5% retention money to be held up for 6 months from the date of successful completion of the work.
7. Please note that you have to mandatorily submit all necessary documents (as per law) along with your bills being conclusive proof that you are fully GST compliant as will be required from time to time failing to which this work order will be unilaterally cancelled by the Club and the Club will not be responsible for any financial loss incurred on your behalf.
8. No escalation in prices allowed. Rate to remain firm till completion of work/contract.
9. Debris to be stacked within 150 m from work site for disposal.
10. All safety protocols to be strictly maintained during work at site.

Swapan Kumar Santra
Chief Manager- Civil

Signature of Contractor with seal
