

Notice Inviting Quotation:

Sealed quotation are invited for the following works from experienced bonafied and resourceful outside /inside contractors for the under mentioned works by the The Chief Executive Office of The Tollygunge Club Ltd. 120 Deshapran Sasmal Road, Kolkata- 700 033.

Name of the work: Construction of Temporaty Shmiana of 3000 sft at Club Main Lawn on hire basis for the period 6th April'2025 to 15th July'2025 inside Tollygunge Club Premises ,120 D P S Road, Kolkata- 700 033 .

Sl no.	Description of work	Unit	Qty	Rate in figure in Rs.	Rate in words	Total Amount in Rs.	Remarks
	Making shed structure shamiana of 3000 sft as per following specification:						
1	Size of Shamiana: Length 60 feet, width 50 feet & Ceiling height-11 feet.	no	1				
2	Structure Covering: The existing main lawn bar also will be used to cover the temporary Shamiana.						
3	MS (Mild Steel) Structure:						
I	Proper foundation with columns, beams, and lintels to ensure structural integrity.						
II	Designed to withstand "nor-wasters" (likely strong winds or storms) during April.						
4	Roof Covering: Fire retardant materials used for safety, ensuring rain proofing as well.						
5	Flooring: Wooden floor (5" ht from existing floor) with a synthetic carpet on top.						
6	Wall and Ceiling:						
I	False ceiling and wall made from fire-retardant jute, with a color that has been pre-approved.						
II	East and south sides will be partially covered with jute walling for added protection.						
7	Electrical Setup:						
I	Electrical work will be done with proper cables.						
II	Light fittings will be installed for illumination.						
III	Ceiling fans will be provided for ventilation.						
8	Plug Points: Sufficient plug points will be installed based on the power needs of the Shamiana.						
	Total Amount (Excluding GST) Rs.						

Total Amount Rs.

Terms & Condition:

- 1. Sealed quotation to be submitted at Club Office 1st floor on or before 20th March,25.**
2. Completion time : 10 days.
3. Payment will be made against RA bill/ Final bill.
Department of the Club.
5. Current ESI & PF chalan to be submitted with each bill.
6. Incase the work is not completed on or before the date of completion stated above a penalty of 0.5% of the total bill value will be deducted per week of the incomplete portion of work up to a
7. Please note that you have to mandatorily submit all necessary documents (as per law) along with your bills being conclusive proof that you are fully GST compliant as will be required from time to time failing to which this work order will be unilaterally cancelled by the Club and the Club will not be responsible for any financial loss incurred on your behalf.
8. All safety Protocols to be strickly followed during work.

Swapan Kumar Santra
GM- Projects & Maintenance

Signature of Contractor with seal